

حکومت پاکستان  
وزارت امور کشمیر و گلگت - بلتستان  
اسلام آباد

## ٹینڈر نوٹس

گوجرانوالہ اور جہلم میں درج ذیل کام کے لئے معروف فرمز/گورنمنٹ کنٹریکٹرز سے سربمہر ٹینڈرز مطلوب ہیں۔ تفصیلی ٹینڈرز -/1000 Rs. (ناقابل واپسی) کی ادائیگی پر دفتر جموں اینڈ کشمیر ریفرنڈو چیئرمین ہیلپٹیشن آرگنائزیشن، روم نمبر 134، "R" بلاک، پاک سیکرٹیریٹ، اسلام آباد سے دفتری اوقات کے دوران حاصل کئے جاسکتے ہیں

نمبر شمار	کام کی تفصیل	مدت تکمیل
1	کشمیر کالونی، تھیری سنسی گوجرانوالہ میں اوپن پلاسٹ کے اطراف باؤنڈری وال (65 فٹ لمبائی اور 50 فٹ چوڑی) کے ساتھ (8 فٹ اونچائی) کی تعمیر مع آئرن (10x6) گیٹ	30 یوم
2	کشمیر کالونی، رتھیاں، جہلم میں اوپن پلاسٹ کے اطراف باؤنڈری وال (40 فٹ لمبائی) کے ساتھ (8 فٹ اونچائی) کی تعمیر	30 یوم

(نوٹ: ادائیگی کمیٹی کی جانب سے میٹرل چیک کرنے اور کام کی تکمیل کے بعد کی جائے گی)

ٹینڈرز 03-04-2018 کو دن 11:00 بجے تک وصول اور کنٹریکٹرز یا ان کے نمائندوں کی موجودگی میں اسی دن دفتر جموں اینڈ کشمیر ریفرنڈو چیئرمین ہیلپٹیشن آرگنائزیشن، روم نمبر 134، "R" بلاک، پاک سیکرٹیریٹ، اسلام آباد میں کھولے جائیں گے۔ ٹینڈر لازمی طور پر بولی کی کل رقم کے 2% زر بیعانہ بشکل کال ڈپازٹ/ بینک ڈرافٹ (قابل واپسی) بحق چیئرمین الاٹمنٹ کمیٹی جموں و کشمیر ریفرنڈو چیئرمین ہیلپٹیشن آرگنائزیشن، روم نمبر 12350002482201 ایچ بی ایل، "Q" بلاک، پاک سیکرٹیریٹ برانچ، اسلام آباد جاری کیا گیا ہو، موصول ہونا چاہئے۔ زر بیعانہ کے بغیر/ ڈاک کے ذریعے ارسال کئے جانے والے ٹینڈرز وصول/ زبردستی لائے جائیں گے۔ تمام سیکس حکومتی قوانین کے تحت منہا کئے جائیں گے۔

اسٹنٹ ایڈمنسٹریٹو آفیسر

جموں اینڈ کشمیر ریفرنڈو چیئرمین ہیلپٹیشن آرگنائزیشن،

"R" بلاک، پاک سیکرٹیریٹ، اسلام آباد

PID (I) 5111/17

15 cm x 3 col

## **TERMS AND CONDITIONS.**

The work will be done in specific time and according to the specification as mentioned in the tender document.

The work will be required to be completed within 30-days.

The completion of work will be certified by the Joint Secretary, M/o KA&GB or his nominee.

No extra work will be involved, if any unforeseen reason it is found to be un-available, prior approval of the Ministry will be required.

Since the work is to be done at specific height, the owner will not responsible for any mis-hap or compensation to the workman engaged by the contractor.

In case of any delay in completion of work, the Joint Secretary, M/o KA&GB will be competent to enforce any penalty at his own will.

10% security will be deducted from the bill and will be released after 3 months commencing from the date of completion, on the entire satisfaction of the Ministry.

The payment will be made in one installment on the completion of work. The payment will be released on verification by the Joint Secretary, M/o KA&GB on the report of Sub-Engineer, J&K State Property, Rawalpindi that the work has been completed in accordance with the prescribed specifications.

In the event of the tender being submitted by a firm, it must be signed separately by each member thereof, or in the event of the absence of any partner, it must be signed on this behalf by a person holding a power –of-attorney authorizing him to do so. Such power-of- attorney to be produced with the tender, and it must disclosed that the firm is duly registered under the Pakistan partnership Act.

Any person who submits a tender shall fill up the attached printed form stating at what rate he is willing to undertake each items of the work.

The contractor shall submit the bill on the printed forms of his firm in the office of the Assistant Administrative Officer, J&K RRO, Ministry of KA&GB Room No. 134 1st floor Pak Secretariat, Islamabad and the charges in the bill shall always entered at the rate specified in the tender.

In any case in which under clauses of this contract the contractor shall have rendered himself liable to pay compensation amounting to the whole of his security deposit. The Joint Secretary, M/o KA&GB, shall have power to adopt any of the following course as he deem best suited to be interest of Governments.

To rescind the contract (of which rescission notice in writing the contractor under the hand of Joint Secretary, M/o KA&GB shall be conclusive evidence) and which case the security deposit of the contract shall stand forfeited, and be absolutely at the disposal of the Government.

To employee labour paid by the contractor and to supply material to carry out of the work or any of the work part, debiting the contractor with cost of the material and crediting his with the value of the work done, in all respects in the same manner and at the same rates of had been carried out by contractor, the contractor under the terms and conditions of his contract, the certificate of the Joint Secretary, M/o KA&GB as to the value of the work done shall be final and conclusive against the contractor.

To measure up the work done by the contractor, and to take such part, thereof as shall be un-executed of his hands, and to give it to another contractor to complete in which case any expenses which may be incurred in excess of the sum which would have been executed by him (of the amount of which excess the certificate in writing of the Assistant Administrative Officer, J&K RRO / SO(K-II), Ministry of KA&GB shall be final and conclusive ) shall be born and paid by the original contractor, and may deducted from any money due to him by Government under the contractor, otherwise, or from his security deposit or the proceeds of sale therefore, or a sufficient part thereof.

Income Tax will be deducted from the bills from as par limit fixed by the Government unless an exemption certified is provided by the Contractor.

**CONTRACTOR SIGNATURE** \_ \_\_\_\_\_

**TENDER DOCUMENTS FOR THE CONSTRUCTION OF BOUNDARY WALL KASHMIR COLONY THERI SANSI GUJRANWALA.**

Sr. No	Detail of Work	Qty _	Rate _	Unit _	Amount.
1.	Excavation O/soil for const of B/wall .	2415cft	_____	_____	_____
2.	P/L P.C.C (1:4:8)for bed	345 cft	_____	_____	_____
3.	P/L P:C:C (1:2:4)	345 cft	_____	_____	_____
4.	Pucca brick work (1:5) in ground floor	488 cft	_____	_____	_____
5.	B.B (1:5)	517 cft	_____	_____	_____
6.	DPC 3'' thick	65 cft	_____	_____	_____
7.	B.B (1.5)	900 cft	_____	_____	_____
8.	B. B (1.5)'	1380 cft	_____	_____	_____
9.	P/F of steel (18 SWG) back side of main Gate	60 cft	_____	_____	_____

i/c paining & welding charges etc. complete in all respect.

---

G. Total :-

**TENDER DOCUMENTS FOR THE CONSTRUCTION OF BOUNDARY WALL KASHMIR COLONY JHELUM .**

Sr. No	Detail of Work	Qty _	Rate _	Unit _	Amount.
1.	Excavation O/soil for const of B/wall.	1365 cft	_____	_____	_____
2.	P/L P.C.C (1:4:8)for bed	195 cft	_____	_____	_____
3.	P/L P:C:C (1:2:4)	195 cft	_____	_____	_____
4.	Pucca brick work (1:5) in ground floor	276 cft	_____	_____	_____
5.	B.B (1:5)	293 cft	_____	_____	_____
6.	DPC 3'' thick	37 cft	_____	_____	_____
7.	B.B (1.5)	720 cft	_____	_____	_____
8.	B. B (1.5)'	780 cft	_____	_____	_____

---

G. Total :-